WATER TREATMENT PLANT

STORM WATER BASIN RELOCATION

NOTICE TO CONTRACTORS

- CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS
 FOR PUBLIC WORKS CONSTRUCTION AND THE APPLICABLE REQUIREMENTS OF THE STATE OF
 CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS, 2018 EDITION
 EXCEPT AS MODIFIED BY THE CITY'S STANDARD DRAWINGS OR THE SPECIAL PROVISIONS
- 2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE STARTING WORK.
- 3. ALL A.C. PAVEMENT AND CONCRETE IMPROVEMENTS TO BE JOINED SHALL BE SAWCUT.
- 4. THE ENGINEER DOES NOT WARRANT THE ACCURACY OF SCALED DIMENSIONS ON ANY PLAN. ALL DIMENSIONS SHALL BE AS DESIGNED ON THE PLANS. THE CONTRACTOR SHALL PROTECT ALL PUBLIC AND PRIVATE PROPERTY.
- DURING THE PERFORMANCE OF WORK DONE UNDER THE CONTRACT, THE CONTRACTOR SHALL
 TAKE THE NECESSARY PRECAUTIONS TO AVOID ANY DAMAGE TO ANY STRUCTURES ADJACENT TO
 THE PROJECT BOUNDARIES.
- 6. EXISTING UTILITIES SHOWN ARE BASED ON AVAILABLE RECORDS OR PARENT UTILITY COMPANIES AND MAY NOT ACCURATELY REPRESENT THEIR ACTUAL LOCATIONS. PRIOR TO BEGINNING ANY CONSTRUCTION, THE CONTRACTOR SHALL VERIFY THE ACTUAL LOCATIONS (VERTICAL AND HORIZONTAL) OF ALL UTILITIES, IN THE FIELD OR COORDINATE SUCH INDEPENDENT VERIFICATION WITH THE PARENT UTILITY COMPANIES AND PROVIDE THE CITY WITH THE POTHOLE INFORMATION. THE CONTRACTOR SHALL PROTECT IN PLACE OR COORDINATE WITH PARENT COMPANY FOR THE RELOCATION OF CONFLICTING UTILITIES ENCOUNTERED DURING CONSTRUCTION.
- 7. THE CONTRACTOR SHALL NOTIFY UNDERGROUND SERVICE ALERT (USA) AT 811 TWO WORKING DAYS PRIOR TO ANY EXCAVATION.
- 8. A VISIT TO THE SITE IS REQUIRED. VERIFY ALL CONDITIONS PRIOR TO SUBMITTING A BID.
- 9. EXTRA WORK AND/OR CHANGES TO BE APPROVED IN WRITING BY THE CITY PRIOR TO COMMENCEMENT OF WORK.
- OBTAIN ALL PERMITS REQUIRED TO COMPLETE THE WORK SPECIFIED PRIOR TO COMMENCEMENT OF WORK.



CONTRACTOR NOTES

- 1. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PROTECT ALL EXISTING SURVEY MONUMENTS, LOT STAKES (TAGGED), OR BENCH MARKS. ANY MONUMENT DISTURBED DURING CONSTRUCTION SHALL BE PERPETUATED PER THE PROFESSIONAL LAND SURVEYOR'S ACT, BUSINESS AND PROFESSIONS CODE 8771, AT THE CONTRACTORS EXPENSE.
- 2. CONTRACTOR IS RESPONSIBLE FOR SUBMITTING A TEMPORARY TRAFFIC CONTROL PLAN TO THE CITY OF CORCORAN FOR APPROVAL.
- 3. NOTIFY THE ENGINEER OF ANY DISCREPANCIES BETWEEN THE PLANS AND THE PROJECT SITE.
- 4. CONTRACTOR IS RESPONSIBLE FOR PREPARING & SUBMITTING A WATER POLLUTION CONTROL PLAN (WPCP) TO THE ENGINEER FOR APPROVAL FOR ALL CONSTRUCTION ACTIVITIES PRIOR TO THE BEGINNING OF WORK, AND REVISED TO REMAIN CURRENT THROUGHOUT THE PROJECT.
- 5. CONTRACTOR TO PROVIDE 2 WEEKS NOTICE (EXCLUDING WEEKENDS), 3 DAY NOTICE AND 24 HOUR NOTICE TO PROPERTY OWNERS AND RESIDENTS PRIOR TO COMMENCING CONSTRUCTION WORK, NOTIFICATION TO BE BY LETTER AND SHALL BE APPROVED BY THE ENGINEER.
- 6. CONTRACTOR SHALL RESTORE ALL FACILITIES DAMAGED BY CONSTRUCTION OPERATION TO THEIR ORIGINAL CONDITION AT NO ADDITIONAL COST. NO MATERIAL MAY BE STORED IN PUBLIC RIGHT OF WAY.
- 7. TRAFFIC CONTROL DURING CONSTRUCTION SHALL BE THE CONTRACTORS RESPONSIBILITY AND IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL SUBMIT A WRITTEN TRAFFIC CONTROL & SIGNING PLAN (INCLUDING STREET CLOSURE DETAILS) TO THE ENGINEER WITHIN TEN (10) WORKING DAYS AFTER AWARD OF CONTRACT.
- 8. THE CONTRACTOR SHALL PROVIDE ALL LIGHTS, SIGNS BARRICADES, TEMPORARY RAMPS, FLAGMEN AND OTHER DEVICES TO PROVIDE VEHICULAR AND PEDESTRIAN SAFETY.
- 9. CONTRACTOR SHALL PROTECT ALL UTILITY STRUCTURES, AND SURVEY MONUMENTS WITHIN THE WORK AREAS. THE CONTRACTOR SHALL REVIEW THE WORK SITES PRIOR TO SUBMISSION OF BIDS.
- 10. RIGHT OF WAY LINES ARE SHOWN AT APPROXIMATE LOCATIONS.
- 11. IT SHALL BE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY LOCATION, ELEVATIONS, OF EXISTING FACILITIES AND TO IMMEDIATELY NOTIFY THE ENGINEER OF ANY FIELD CONFLICTS OR OMISSIONS.
- 12. THE CONTRACTOR SHALL FURNISH A SELF-LOADING MOTOR SWEEPER WITH SPRAY NOZZLE AND OPERATE AT LEAST ONCE A DAY AND MORE AS NECESSARY TO CONTROL DUST CONDITIONS.
- 13. THE CONTRACTOR SHALL MAINTAIN ACCESS TO RESIDENCES AND BUSINESSES THROUGHOUT THE LIFE OF THE CONTRACT.
- 14. ANY DAMAGE TO THE EXISTING FACILITIES INCLUDING, BUT NOT LIMITED TO, TRESS, LANDSCAPING, IRRIGATION, FENCES, WALL. SIDEWALK, ANY OTHER PAVEMENT SURFACES SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE. CONTRACTOR SHALL RESTORE ANY AND ALL PAVEMENT AND OTHER FACILITIES OUTSIDE LIMITS OF WORK AFFECTED BY THE CONSTRUCTION OPERATIONS AT NO ADDITIONAL COST.
- 15. BIDDERS SHOULD NOTE PRESENCE OF OVERHEAD UTILITIES IN THE WORK AREA ALL OVERHEAD UTILITIES MAY NOT BE SHOWN ANY IF SHOWN, MAY BE IN THEIR APPROXIMATE ALIGNMENT. AS PART OF THEIR PRE-BID INSPECTION, BIDDERS SHALL NOTE THE TYPE ANY LOCATION OF OVERHEAD UTILITIES IN THE PROPOSED WORK AREA BIDDER'S PRICE SHALL INCLUDE PROVISIONS FOR WORKING IN AREAS WHERE OVERHEAD UTILITIES EXIST AT THE TIME OF BIDDING, WHETHER SHOWN ON THE PLANS OR NOT, AND NO ADDITIONAL COMPENSATION IS ALLOWED.

TEMPORARY REPAVING REQUIREMENTS

- A. THE CONTRACTOR SHALL FURNISH, PLACE AND COMPACT TWO (2)-INCHES OF COLD PATCH AS TEMPORARY PAVEMENT SURFACE OVER ALL BACKFILL AREAS CREATED FOR PIPELINE AND STRUCTURE INSTALLATION LOCATED IN ROADWAYS OR DRIVEWAYS. THIS SURFACE SHALL BE MAINTAINED BY THE CONTRACTOR UNTIL PERMANENT SURFACE RESTORATION HAS BEEN PERFORMED.
- B. SHOULD THE CONTRACTOR REMOVE EXISTING PAVEMENT BEYOND THE WIDTH SPECIFIED OR DETAILED ON THE PLANS, OR SHOULD PAVEMENT BE DISTURBED FROM SETTLEMENT, SLIDES OR OTHER CONSTRUCTION ACTIVITIES, HE SHALL SAWCUT BACK THE PAVEMENT AND PROVIDE TEMPORARY PAVING IN THESE AREAS.

BENCHMARKS

COORDINATES ARE REFERENCED TO THE CCS83, ZONE 4 NAD83 (NSRS2007) EPOCH 2007.00. VERTICAL DATUM IS NAVD88 VIA GEOID09 REFERENCED TO GEODETIC DATUM EPOCH OF 2007.00 AS PUBLISHED IN CAHST AUTHORITY "RFP NO. HSR 13-57-BOOK IV, PART G.4 RECORD OF SUPPLY AND CONTROL MONUMENT DATA.

CONTROL POINTS

NORTH SIDE OF ORANGE AVENUE

CONTROL POINT 1:

CHISELED 'X' LOCATED ON THE TOP OF MANHOLE NEAR WATER TANK

CONTROL POINT 2:
CHISELED 'X' LOCATED ON THE TOP OF FOOTING ON ELECTRICAL TOWER ON THE

CONTROL POINT 3:

CHISELED 'X' LOCATED ON THE EASTSIDE OF A CONCRETE CULVERT BOTTOM HEADWALL

CONTROL POINT 4:

CHISELED 'X' LOCATED ON THE NORTH EASTSIDE OF A CONCRETE HEADWALL CROSSING THE IRRIGATION CANAL

ESTIMATED EARTHWORK QUANTITIES

UT (C.Y.): 3,398 ILL (C.Y.): 0

NET (C.Y.): 3,398 <CUT>

QUANTITIES ARE SHOWN AS ESTIMATES ONLY.
QUANTITIES SHALL NOT BE TAKEN AS EXACT QUANTITIES
CONTRACTOR SHALL BE RESPONSIBLE TO COMPLETE
INDEPENDENT QUANTITY TAKE OFF AND VERIFY

EARTHWORK MATERIAL TO COMPLETE THE PROJECT

CITY & ENGINEER CONTACTS

PUBLIC WORKS DIRECTOR CIVIL

JOSEPH FAULKNER ORFIL MUNIZ, PE, QSD
CITY OF CORCORAN A&M CONSULTING ENGINEERS
832 WHITLEY AVE 220 N LOCUST AVE
CORCORAN, CA 93212 VISALIA, CA 93291
(559) 992-2151 EXT. 2210 (559) 429-4747

PROJECT UTILITY CONTACTS

PG&E FRONTIER COMMUNICATION

JEFF HEIDNGER SOCRATES LUNA

705 "P" ST 1359 "G" STREET,

FRESNO, CA 93760 REEDLEY, CA 93654

(559) 263-7368 (559) 637-0666

SOUTHERN CALIFORNIA GAS CO
CHAD MUELLER
MICHAEL CORRAL
404 N TIPTON STREET
(559) 217-9003
VISALIA, CA 93292
(559) 739-2241

CITY OF CORCORAN WATER AND WASTEWATER
JOSEPH FAULKNER
832 WHITLEY AVE
CORCORAN, CA 93212
(559) 992-2151 EXT. 2210

INDEX OF PLANS

TS - 1.01 - TITLE SHEET
TS - 1.02 - GENERAL NOTES AND LEGEND
DM - 1.01 - DEMOLITION PLAN
CD - 1.01 - SITE PLAN
CD - 1.02 - PROFILE ALIGNMENTS
GR - 1.01 - GRADING AND DRAINAGE PLAN
DS - 1.01 - DETAILS

PIPELINE TRENCH EXCAVATION NOTES

- A. THE CONTRACTOR SHALL EXCAVATE, MAINTAIN AND BACKFILL ALL EXCAVATION NECESSARY FOR COMPLETING THE WORK UNDER THE CONTRACT. UNLESS OTHERWISE SPECIFIED OR APPROVED, EXCAVATION SHALL BE OPEN
- B. TRENCHES SHALL BE EXCAVATED TO THE NECESSARY WIDTH AND DEPTH, AS SHOWN ON THE DRAWINGS AND AS REQUIRED FOR THE SAFE INSTALLATION OF THE UTILITY ETC.
- C. THE SIDES OF THE TRENCHES SHALL BE PRACTICALLY PLUMB AND SHALL NOT BE SLOPED UNLESS APPROVED IN WRITING BY THE ENGINEER. TRENCH SIDES SHALL BE SUPPORTED OR SHEETED AS REQUIRED TO PROTECT PAVEMENT SURFACES, CURBING, UTILITIES, ETC., AND REQUIRED FOR SAFETY. SAFETY REGULATIONS SHALL BE AS REQUIRED BY STATE SAFETY CODES AND OSHA.
- D. IN PAVED AREAS, THE CONTRACTOR SHALL REMOVE THE PAVING ONLY AS NECESSARY FOR THE EXCAVATION OF THE TRENCH OR AS DETAILED. PAVEMENT EDGES AT THE TRENCH SHALL BE SAW CUT NEAT AND STRAIGHT PRIOR TO THE START OF ANY EXCAVATION. SHOULD THE PAVEMENT DAMAGE RESULT FROM CAVE-INS, SETTLEMENT, ETC., HE SHALL REPLACE SUCH PAVING AT HIS OWN EXPENSE.
- E. THE EXCAVATION OF ALL TRENCHES SHALL BE FULLY COMPLETED AT LEAST TWENTY (20) FEET IN ADVANCE OF PIPE LAYING, UNLESS OTHERWISE AUTHORIZED OR DIRECTED. THE ENGINEER OR OWNER MAY REQUIRE THE BACKFILLING OF OPEN TRENCH, OVER COMPLETED PIPELINES, OR AHEAD OF THE PIPE LAYING OPERATION, IF IN HIS JUDGEMENT, SUCH ACTION IS NECESSARY
- F. SHOULD WORK BE STOPPED FOR ANY REASON AND ANY EXCAVATION IS LEFT OPEN FOR AN UNREASONABLE LENGTH OF TIME, THE CONTRACTOR SHALL REFILL THE EXCAVATION AT HIS OWN EXPENSE IF SO DIRECTED, AND SHALL NOT REOPEN THE EXCAVATION UNTIL HE IS READY TO COMPLETE THE FACILITY. SHOULD THE CONTRACTOR REFUSE OR FAIL TO REFILL ANY EXCAVATION COMPLETELY WITHIN EIGHT (8) HOURS AFTER A PROPER NOTICE, THE OWNER-SHALL BE AUTHORIZED TO DO THE WORK AND EXPENSES RESULTING SHALL BE PAID BY THE CONTRACTOR.
- G. THE CONTRACTOR SHALL COMPLETE EXCAVATION AS NEARLY AS PRACTICABLE TO THE LINES OF THE UTILITY TO BE INSTALLED AS DETAILED. ALL CAVITIES IN THE BOTTOM OF THE TRENCH SHALL BE FILLED TO THE REQUIRED LEVEL WITH COMPACTED CRUSHED STONE OR GRAVEL.
- H. EXCAVATED MATERIALS SHALL BE GRADED, HAULED, STORED AND PROTECTED AS SUCH MATERIAL FOUND SUITABLE WILL BE REQUIRED FOR BACKFILLING, REPAVING OR OTHER PURPOSES. MATERIAL CLASSIFIED AS UNSUITABLE SHALL BE DISPOSED OF BY THE CONTRACTOR.
- I. EXCAVATED MATERIALS SHALL NOT BE PLACED ON PRIVATE PROPERTY, UNLESS WRITTEN PERMISSION IS OBTAINED FROM THE PROPERTY OWNER
- J. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO CURB, GUTTER, SIDEWALK, TRAFFIC CONTROL DEVICES, PAVEMENT MATERIAL. ANY DAMAGE RESULTING DIRECTLY OR INDIRECTLY SHALL BE REPLACED IN KIND BY THE CONTRACTOR. THE REUSE OF DISTURBED CURB, GUTTER OR SIDEWALK IS PROHIBITED. NEW SECTIONS SHALL BE INSTALLED TO THE NEAREST UNDISTURBED CONTROL JOINT.

PIPELINE TRENCH BACKFILL

- A. MATERIALS EXCAVATED FROM THE TRENCH SHALL BE USED FOR TRENCH BACKFILL, PROVIDED THAT, IN THE OPINION OF THE ENGINEER OR OWNER, THE EXCAVATED MATERIAL IS SUITABLE FOR THIS PURPOSE. BACKFILL MATERIAL SHALL BE FREE FROM LARGE LUMPS AND STONES HAVING ANY DIMENSION GREATER THAN TWO (2)-INCHES
- B. SUITABLE MATERIAL, AS APPROVED BY THE ENGINEER, SHALL BE CAREFULLY DEPOSITED IN THE TRENCH BY METHODS WHICH WILL NOT DAMAGE OR DISTURB THE PIPE OR STRUCTURE. BACKFILL MATERIAL SHALL BE PLACED IN EIGHT (8)-INCH LOOSE LAYERS. CARE SHALL BE TAKEN IN THE USE OF MECHANICAL TAMPERS NOT TO INJURE OR MOVE THE PIPE OR TO CAUSE THE PIPE TO BE SUPPORTED UNEVENLY.
- C. ALL BACKFILL MATERIAL SHALL BE COMPACTED TO 95% OF MAXIMUM DENSITY BETWEEN MINUS TWO TO PLUS TWO (2) PERCENT OF OPTIMUM MOISTURE CONTENT AS DETERMINED BY THE MODIFIED PROCTOR TEST, ASTM D1557. MATERIALS CONTAINING AN EXCESS OF MOISTURE SHALL BE PERMITTED TO DRY UNTIL THE MOISTURE CONTENT IS WITHIN THE SPECIFIED RANGE. MATERIALS TOO DRY SHALL BE WETTED UNIFORMLY UNTIL THE MOISTURE CONTENT IS IN THE SPECIFIED RANGE.
- D. NO COMPACTING SHALL BE DONE WHEN THE MATERIAL IS TOO WET TO BE COMPACTED PROPERLY. AT SUCH TIMES THE WORK SHALL BE SUSPENDED UNTIL THE BACKFILL MATERIALS HAVE DRIED OUT SUFFICIENTLY TO PERMIT PROPER COMPACTION OR SUCH OTHER PRECAUTIONS SHALL BE TAKEN AS MAY BE NECESSARY TO OBTAIN PROPER COMPACTION. THE CONTRACTOR IS RESPONSIBLE FOR HAULING, STORING AND DRYING OF EXCAVATED MATERIAL TO BE USED IN BACKFILL OPERATIONS.
- E. THE ENGINEER MAY REQUEST COMPACTION TESTS OF THE BACKFILLED TRENCHES AT ANY TIME DURING CONSTRUCTION OR UPON COMPLETION OF THE BACKFILL OPERATIONS. SUCH TESTING SHALL BE ARRANGED BY THE CONTRACTOR AND PERFORMED BY AN INDEPENDENT TESTING AGENCY APPROVED BY THE ENGINEER. THE CONTRACTOR SHALL PAY THE TESTING LABORATORY FOR ALL TESTS PERFORMED INCLUSIVE OF SAMPLE COLLECTION, PREPARATION AND TRANSPORTATION. IF THE RESULTS OF ANY TESTS SHOW THAT BACKFILLS DO NOT MEET THE SPECIFIED COMPACTION, THE CONTRACTOR SHALL, AT HIS OWN EXPENSE, CORRECT THE CONDITION AS DIRECTED BY THE ENGINEER.
- THE CONTRACTOR SHALL, AT HIS OWN EXPENSE, MAINTAIN ALL REFILLED EXCAVATIONS IN PROPER CONDITION. TRENCH SURFACES SHALL BE RESHAPED WHEN NECESSARY. IF THE CONTRACTOR FAILS TO MAKE REPAIRS WITHIN FORTY-EIGHT (48) HOURS AFTER RECEIPT OF WRITTEN NOTICE FROM THE OWNER, THE OWNER MAY REFILL SAID DEPRESSION WHEREVER NECESSARY AND THE COST OF SO DOING WILL BE PAID BY THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY INJURY OR DAMAGE THAT MAY RESULT FROM LACK OF MAINTENANCE OF ANY REFILLED EXCAVATION AT ANY TIME PRIOR TO FINAL ACCEPTANCE.
- G. ALL UNAUTHORIZED EXCAVATIONS MADE BY THE CONTRACTOR SHALL BE IMMEDIATELY BACKFILLED IN ACCORDANCE WITH THE REQUIREMENTS OF THE SPECIFICATIONS FOR TRENCH BACKFILL, AT THE CONTRACTOR'S EXPENSE.
- H. AFTER COMPLETION OF BACKFILLING, ALL MATERIAL NOT USED, SHALL BE DISPOSED OF, AND ALL PLACES ON THE LINE OF THE WORK SHALL BE LEFT CLEAN AND IN GOOD CONDITION. THIS CLEANING UP SHALL BE DONE BY THE CONTRACTOR. IF HE FAILS TO DO THIS WORK WITHIN A REASONABLE TIME AFTER RECEIPT OF NOTICE, IT WILL BE PERFORMED BY THE OWNER, AND THE COST WILL BE ASSESSED TO THE CONTRACTOR.
- I. NO BACKFILL SHALL BE PLACED AGAINST NEW CONCRETE OR MASONRY STRUCTURES UNTIL PROPERLY CURED. IN THE CASE OF CONCRETE, TEST REPORTS MUST INDICATE THAT A 2500 PSI COMPRESSIVE STRENGTH EXISTS.
- J. THE CONTRACTOR SHALL EXERCISE CAUTION IN BACKFILL AND COMPACTION TO PREVENT DAMAGE TO STRUCTURES
- K. NO TRENCH SHALL BE LEFT OPENED AT THE END OF THE WORKING DAY, UNLESS DIRECTED BY THE ENGINEER. ALL TRENCHES SHALL BE BACKFILLED. NO METAL PLATES ALLOWED FOR THE PROJECT.

DUST CONTROL PLAN REQUIREMENTS

- 1. IDENTIFY THE DUST SOURCES AND DESCRIBE THE DUST CONTROL MEASURES THAT WILL BE IMPLEMENTED BEFORE DURING, AND AFTER ANY DUST GENERATING ACTIVITY FOR THE DURATION OF THE PROJECT. THE CONTRACTOR IS REQUIRED TO SUBMIT PLANS, OBTAIN PERMIT, AND PAY ALL FEES TO THE SAN JOAQUIN VALLEY AIR POLLUTION CONTROL DISTRICT AT LEAST 30 DAYS PRIOR TO COMMENCING THE WORK FOR THE FOLLOWING:
- THE RELOCATION OF MORE THAN 2,500 CUBIC YARDS PER DAY OF MATERIALS ON AT LEAST THREE DAYS.
- 2. OPERATIONS MAY NOT COMMENCE UNTIL THE DISTRICT HAS APPROVED THE DUST CONTROL PLAN. A COPY OF THE PLAN MUST BE ON SITE AND AVAILABLE TO WORKERS AND DISTRICT EMPLOYEES. ALL WORK ON THE SITE IS SUBJECT TO THE REQUIREMENTS OF THE APPROVED DUST CONTROL PLAN. A FAILURE TO ABIDE BY THE PLAN BY ANYONE ON SITE MAY BE SUBJECT TO ENFORCEMENT ACTION. THE CITY OF LEMOORE IS NOT RESPONSIBLE FOR ANY VIOLATION FEES, THE CONTRACTOR SHALL BE RESPONSIBLE TO PAY FOR ALL ASSOCIATED FEES.
- 3. RECORD KEEPING IS REQUIRED TO DOCUMENT COMPLIANCE WITH THE RULES AND MUST BE KEPT FOR EACH DAY ANY DUST CONTROL MEASURE IS USED. THE DISTRICT HAS DEVELOPED RECORD FORMS FOR WATER APPLICATION, STREET SWEEPING, AND "PERMANENT" CONTROLS SUCH AS APPLYING LONG TERM DUST PALLIATIVES, VEGETATION, GROUND COVER MATERIALS, PAVING, OR OTHER DURABLE MATERIALS. RECORDS MUST BE KEPT FOR ONE YEAR AFTER THE END OF DUST GENERATING ACTIVITIES (TITLE V SOURCES MUST KEEP RECORDS FOR FIVE YEARS).



G ENGINEERS



A TREATMENT PLANT
ATER BASIN RELOCA-

STORM WATER B

VISIONS

Ċ

AS SHOWN 221-048 JA BASIN TS.DWG

SCALE: /
JOB NO: 2
QA/QC: .



HEET NO.

TS-1.0

OF

ABREVIATIONS & LEGEND

AB ABV	AGGREGATE BASE ABOVE	LID LIP	LOW IMPACT DEVELOPMENT GUTTER LIP
AC	ASPHALT CONCRETE	LOC	LOCATION
ACP	ASPHALT CONCRETE PAVING/PAVEMENT	LP	LOW POINT
ADJ	ADJACENT	LS	LIFT STATION
AGG	AGGREGATE	LT	LEFT
ALT	ALTERNATE	MAS	MASONRY
\P	ANGLE POINT	MATL	MATERIAL
APPROX	APPROXIMATE	MAX	MAXIMUM
ARCH	ARCHITECT(URAL)	ME MED	MATCH EXISTING
BEL BLDG	BELOW BUILDING	MFG	MEDIUM MANUFACTURING
BLDG BLK	BUILDING BLOCK	MFR	MANUFACTURE(R)
BMP	BEST MANAGEMENT PRACTICE	MH	MANHOLE
BOT	BOTTOM	MIN	MINIMUM
BOW	BACK OF WALK	MISC	MISCELLANEOUS
BR	BOTTOM OF RAMP	ML	MAINLINE
BRG	BEARING	N	NEW
	CONCRETE	NIC	NOT IN CONTRACT
СВ	CATCH BASIN	NO	NUMBER
CF	CUBIC FOOT	NOM	NOMINAL
CI	CAST IRON	NTS	NOT TO SCALE
CITY	CITY OF CORCORAN	OC	ON CENTER
CIP	CAST IN PLACE	OD	OUTSIDE DIAMETER
CL C	CENTERLINE	OG	ORIGINAL GROUND
CLR	CLEAR	OH	OVERHEAD
CMU	CONCRETE MASONRY UNIT	OPP	OPPOSITE
CO	CLEAN OUT	OPT	OPTIONAL
COL	COMMUNICATION	P PA	PAVEMENT DI ANTER AREA
COMM	CONCRETE	PA PCR	PLANTER AREA POINT OF CURVE RADIUS
CONC	CONCRETE CONSTRUCTION	PERF	PERFORATE(D)
CONT	CONTINUE, CONTINUOUS	PERP	PERPENDICULAR
CP	CENTER POINT	PFE	PUBLIC FACILITIES EASEMENT
OF CP#	CONTROL POINT #	PL	PROPERTY LINE
CR	CURB RETURN	POB	POINT OF BEGINNING
CTC	CENTER TO CENTER	POC	POINT OF CONNECTION
CTR	CENTER	PRC	POINT OF REVERSE CURVE
DAS	DIRECTION AS SHOWN	PROP	PROPOSED
DET	DETAIL	PSI	POUNDS PER SQUARE INCH
OF .	DRINKING FOUNTAIN	PT	POINT
OI .	DRAIN INLET	PTL	PRESSURE TREATED LUMBER
DIA	DIAMETER	PUE	PUBLIC UTILITY EASEMENT
DIAG	DIAGRAM	PVC	POLYVINYL CHLORIDE
OIM	DIMENSION	R, RAD	RADIUS
OIP	DUCTILE IRON PIPE	REBAR REF	REINFORCING BAR REFERENCE
DS DWC	DOWN SPOUT	REM	
DWG EA	DRAWING EACH	REM REQ'D	REMOVE REQUIRED
=A ≣J	EXPANSION JOINT	REV	REVISION(S), REVISED
LECT	ELECTRICAL	RH	RIGHT HAND
ELEV	ELEVATION	ROW	RIGHT-OF-WAY
ENCL	ENCLOSURE	RT	RIGHT
ΕP	EDGE OF PAVEMENT	R/W	RIGHT-OF-WAY
ΕQ	EQUAL	R(XX.X)	RADIUS
EQUPT	EQUIPMENT	SCH	SCHEDULE
ESMT	EASEMENT	SD	STORM DRAIN
EXIST	EXISTING	SDMH	STORM DRAIN MANHOLE
E)	EXISTING	SF	SQUARE FEET
AB	FABRICATION	SG	SUBGRADE
ВО	FURNISHED BY OTHERS	SHT	SHEET
F	FINISHED FLOOR	SIM	SIMILAR
FFE	FINISHED FLOOR ELEVATION	SL	SLOPE
-G	FINISHED GRADE	SPEC	SPECIFICATION(S)
=IN 	FINISH(ED)	SQ	SQUARE SANITARY SEWER
FL	FLOW LINE	SS S/S	SANITARY SEWER
FOC	FACE OF CONCRETE FACE OF FINISH	S/S SSFM	STAINLESS STEEL SANITARY SEWER FORCE MAI
FOF FOM	FACE OF FINISH FACE OF MASONRY	SSFM	SANITARY SEWER FORCE MAI
-OM -OS	FACE OF STEP	ST	STREET SEWER MANHOLE
-05 -ND	FOUNDATION	STA	STATION
-ND -S	FINISHED SURFACE	STD	STANDARD
ST	FINISHED SURFACE TURF	STL	STEEL
FTG	FOOTING	STRUC	STRUCTURE/STRUCTURAL
=UT	FUTURE	SURF	SURFACE
GΑ	GAGE, GAUGE	SWCL	SIDEWALK CENTERLINE
ЭB	GRADE BREAK	SYS	SYSTEM
GKT	GASKET	SYN	SYNTHETIC
GLV	GALVANIZED	TBC	TOP BACK OF CURB
GPH	GALLONS PER HOUR	TC	TOP OF CURB
GPM	GALLONS PER MINUTE	TF	TOP OF FOOTING
GR ID	GRATE	TG	TOP OF GRATE
HB IC	HOSE BIB	TR	TOP OF STEP
HCAR	HANDICARDED	TS TW	TOP OF STEP
HCAP	HANDICAPPED	TW	TOP OF WALL
HDB IEV	HEADBOARD	TYP	TYPICAL
HEX HOR	HEXAGONAL	UON VAR	UNLESS OTHERWISE NOTED
HOR HD	HORIZONTAL	VAR	VARIES
dΡ uπ	HIGH POINT	VERT W	VERTICAL
TYD TYD	HEIGHT	W	WATER
HYD	FIRE HYDRANT	W/	WITHOUT
D NT	INSIDE DIAMETER	W/O WS	WITHOUT WATER SERVICE
NT	INTERSECTION INVERT	WV	WATER SERVICE WATER VALVE
NIV		VVV	******
		\bigcirc	AT
RR	IRRIGATION	@ Ø	AT DIAMETER
NV RR JT		_	DIAMETER

S=0.XXXX PROPOSED SLOPE IN DECIMAL

LAG BOLT LEFT HAND


	EXISTING RIGHT-OF-WAY
	DEMOLITION / SAWCUT LIMITS
(GAS2) —	EXISTING 2" GAS UTILITY
(GAS4)	EXISTING 4" GAS UTILITY
(GAS6) ———	EXISTING 6" GAS UTILITY
(UU)	EXISTING UNDERGROUND COMM.
(OU)	EXISTING OVERHEAD COMM.
(E)	EXISTING ELECTRICITY UTILITY
(OE)	EXISTING OVERHEAD ELECTRICITY
(W16)	EXISTING 16" WATER LINE
(SS8)	EXISTING 8" SANITARY SEWER
(FM4)	EXISTING 4" SANITARY SEWER FORCEMAIN

GENERAL CONSTRUCTION NOTES

- 1. EXISTING UTILITIES AND EXISTING IMPROVEMENTS MAY BE SHOWN AT APPROXIMATED LOCATIONS DUE TO THE AVAILABLE RECORD INFORMATION AT THE TIME OF PLAN PREPARATION. OTHER UTILITY LINES MAY EXIST. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY ALL EXISTING UTILITIES BY POTHOLING OR LOCATING SERVICES "811" IF FOUND NECESSARY.
- 2. THE CONTRACTOR SHALL NOTIFY ALL CORRESPONDING UTILITY COMPANIES AND CALL "811" AT LEAST 48 HOURS BEFORE THE COMMENCEMENT OF ANY WORK WHICH MAY REQUIRE UTILITY VERIFICATION. ADDITIONALLY, THE CONTRACTOR WILL SUPPLY SOUTHERN CALIFORNIA GAS COMPANY WITH A CONSTRUCTION SCHEDULE AND NOTIFY OF ANY PRE-CONSTRUCTION MEETINGS.
- 3. THE EXISTENCE AND LOCATION OF ANY UNDERGROUND UTILITY OR SUBSTRUCTURE SHOWN ON THESE PLANS WERE OBTAINED BY A SEARCH OF AVAILABLE RECORDS. NO CERTIFICATIONS IS MADE AS THE ACCURACY OR THOROUGHNESS OF THESE RECORDS. APPROVAL OF THESE PLANS BY THE CITY OF CORCORAN DOES NOT CONSTITUTE A REPRESENTATION AS THE ACCURACY OR COMPLETENESS OF LOCATION OR THE EXISTENCE OR NONEXISTENCE OF ANY UNDERGROUND UTILITY OR SUBSTRUCTURE WITHIN THE LIMITS OF THE PROJECT.
- 4. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO REVIEW THE FULL SET OF PLANS FOR ANY DISCREPANCIES AND OMISSIONS PRIOR TO THE COMMENCEMENT OF WORK. IF ANY DISCREPANCIES BETWEEN THESE PLANS AND THE FIELD ARE IDENTIFIED, THE CONTRACTOR SHALL NOTIFY THE ENGINEER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY WORK NOT IN CONFORMANCE WITH THE PLANS OR IN CONFLICT WITH ANY CODE.
- 5. AN APPROVED SET OF PLANS MUST BE AVAILABLE ON THE JOB SITE AT ALL TIMES.

OF ANY NATURE.

- 6. THE CONTRACTOR SHALL POSSESS THE CLASS (OR CLASSES) OF LICENSE AS SPECIFIED IN THE "NOTICE TO BIDDERS."
- 7. ALL WORK SHALL BE PERFORMED IN CONFORMANCE WITH THE PROVISIONS IN THE CALTRANS STANDARD SPECIFICATIONS AND PLANED 2018, ALONG WITH THE CITY OF CORCORAN STANDARD DRAWINGS AND THE LATEST VERSION OF THE
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL MATERIALS, FABRICATIONS, EQUIPMENT, APPLIANCES, TRANSPORTATION, SERVICES AND LABOR NECESSARY FOR THE CONSTRUCTION, ERECTION AND INSTALLATION OF ALL WORK INDICATED ON THESE DRAWINGS AND/OR OUTLINED IN EACH SECTION OF THE SPECIFICATIONS.
- 9. FOR THE DURATION OF THE WORK, THE CONTRACTOR SHALL PROVIDE, INSTALL AND MAINTAIN, AS MAY BE REQUIRED, ALL NECESSARY BARRICADES AND RAILINGS, LIGHTS, WARNING SIGNS AND SIGNALS, AND SHALL TAKE ALL OTHER PRECAUTIONS AS MAY BE REQUIRED TO SAFEGUARD PERSONS, THE JOB SITE AND ADJOINING PROPERTY, AGAINST INJURIES AND DAMAGE
- 10. THE CONTRACTOR AND EACH SUBCONTRACTOR SHALL GIVE THEIR PERSONAL ATTENTION TO THE WORK; BE RESPONSIBLE FOR THE LAYOUT AND CORRECTNESS OF THEIR WORK AND COOPERATE WITH EACH OF THE VARIOUS TRADES TO OBTAIN A NEAT FINISHED AND WORKMANLIKE JOB.
- 11. THE CONSTRUCTION CONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, THE CONSTRUCTION CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS.
- 12. TO THE FULLEST EXTENT PERMITTED BY LAWS AND REGULATIONS, CONTRACTOR SHALL INDEMNIFY AND HOLD HARMLESS OWNER AND ENGINEER, AND THE OFFICERS, DIRECTORS, MEMBERS, PARTNERS, EMPLOYEES, AGENTS, CONSULTANTS AND SUBCONTRACTORS OF EACH AND ANY OF THEM FROM AND AGAINST ALL CLAIMS, COSTS, LOSSES, AND DAMAGES (INCLUDING BUT NOT LIMITED TO ALL FEES AND CHARGES OF ENGINEERS, ARCHITECTS, ATTORNEYS, AND OTHER PROFESSIONALS AND ALL COURT OR ARBITRATION OR OTHER DISPUTE RESOLUTION COSTS) ARISING OUT OF OR RELATING TO THE PERFORMANCE OF THE WORK, PROVIDED THAT ANY SUCH CLAIM, COST, LOSS, OR DAMAGE IS ATTRIBUTABLE TO BODILY INJURY, SICKNESS, DISEASE, OR DEATH, OR TO INJURY TO OR DESTRUCTION OF TANGIBLE PROPERTY (OTHER THAN THE WORK ITSELF), INCLUDING THE LOSS OF USE RESULTING THEREFROM BUT ONLY TO THE EXTENT CAUSED BY ANY NEGLIGENT ACT OR OMISSION OF CONTRACTOR, ANY SUBCONTRACTOR, ANY SUPPLIER, OR ANY INDIVIDUAL OR ENTITY DIRECTLY OR INDIRECTLY EMPLOYED BY ANY OF THEM TO PERFORM ANY OF THE WORK OR ANYONE FOR WHOSE ACTS ANY OF THEM MAY BE LIABLE.
- 13. SHOULD A CONSTRUCTION SURVEY OR CONSTRUCTION STAKING BE NECESSARY, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THIS SERVICE.
- 14. DO NOT SCALE DRAWINGS. IF UNABLE TO LOCATE DIMENSIONS FOR ANY ITEM OF WORK, CONTACT THE ENGINEER FOR DIRECTION BEFORE PROCEEDING.
- 15. ALL DAMAGE TO AREAS AND/OR PROPERTY NOT SPECIFICALLY PART OF THE PROJECT SITE CAUSED DURING CONSTRUCTION ACTIVITIES WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RETURN TO PRE-CONSTRUCTION CONDITIONS.
- 16. CHANGES TO THE APPROVED DRAWINGS AND/OR SPECIFICATIONS SHALL BE MADE BY ADDENDUM OR A CHANGE ORDER SIGNED BY THE ENGINEER AND APPROVED BY THE PUBLIC WORKS/ENGINEERING OFFICIALS
- 17. DUST AND DEBRIS CONTROL MEASURES SHALL BE IMPLEMENTED IN ACCORDANCE WITH THE REQUIREMENTS OF THE SAN JOAQUIN VALLEY UNIFIED AIR POLLUTION CONTROL DISTRICT DISTRICT REGULATION VIII FUGITIVE DUST RULES.
- 18. CONTRACTOR SHALL OBTAIN AND PAY FOR ALL PERMITS NECESSARY TO COMPLETE THE WORK, UNLESS OTHERWISE NOTED.







ER TREATMENT PLANT

WATER BASIN RELOCATION

SHEETTITE:

SNOISIA

Ö


: 221-048 JA BASIN_TS.DWG 2/3/2023

SCALE: JOB NO: QA/QC: FILE: B



SHEET NO

TS-1.02



CONTRACTOR NOTES

- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PRESERVE ALL SURVEY MONUMENTS.
 ANY MONUMENT DISTURBED DURING CONSTRUCTION SHALL BE PERPETUATED PER THE
 PROFESSIONAL LAND SURVEYOR'S ACT, BUSINESS AND PROFESSIONS CODE 8771, AT THE
 CONTRACTORS EXPENSE.
- 2. LOCATIONS OF EXISTING UTILITIES ARE APPROXIMATED. CONTRACTOR TO FIELD VERIFY ALL EXISTING UTILITIES BEFORE COMMENCEMENT OF WORK.

GRADING NOTES

ALL SURFACE VEGETATION AND ANY MISCELLANEOUS SURFACE OBSTRUCTIONS SHOULD BE REMOVED FROM THE PROJECT AREA, PRIOR TO ANY SITE GRADING. IT IS ANTICIPATED THAT STRIPPING OF VEGETATION COULD INVOLVE THE UPPER 3 TO 5 INCHES OF THE SITE. SURFACE STRIPPINGS SHOULD NOT BE INCORPORATED INTO FILL UNLESS THEY CAN BE SUFFICIENTLY BLENDED TO RESULT IN AN ORGANIC CONTENT LESS THAN 3 PERCENT BY WEIGHT (ASTM D2974). STRIPPED TOPSOIL, WITH AN ORGANIC CONTENT BETWEEN 3 AND 12 PERCENT BY WEIGHT MAY BE STOCKPILED AND USED AS NON-STRUCTURAL FILL (I.E. LANDSCAPED AREAS). IF USED IN LANDSCAPE AREAS, SOIL WITH AN ORGANIC CONTENT BETWEEN 3 AND 12 PERCENT SHOULD BE PLACED WITHIN 2 FEET OF FINISHED GRADE AND AT LEAST 5 FEET OUTSIDE OF BUILDING PERIMETERS. SOIL WITH AN ORGANIC CONTENT GREATER THAN 12 PERCENT BY WEIGHT SHOULD BE EXCLUDED FROM FILL.

LEGEND



SITE DEMOLITION AREA - REMOVE AND DISPOSE OF EXISTING SURFACES, CONCRETE, ROCKS, SOLID WASTE, TREES, AND VEGETATION AS SHOWN ON PLAN.




EXISTING FOUND MONUMENT

CONTROL POINT




CONTRACTOR SHALL POTHOLE AND VERIFY SEWER LINE DEPTH WITH ENGINEER BEFORE COMMENCING WORK.



SHEET NO

OF 7



CONSULTING ENGINEERS

STORM WATER BASIN RELOCATION

SHEETTILE:

DEMOLITION PLAN

REVISIONS


NO.

:. JA
BASIN_DEMO.DWG
2/3/2023

SCALE: 1
JOB NO: 2
QA/QC: J
FILE: B
DATE: 2



DM-1.01




SCALE: 1
JOB NO: 2
QA/QC: 4



SHEET NO


CD-1.02



ORANGE AVENUE STA: 10+00 TO 14+47

PLAN VIEW

HORZ: 1" = 20'
VERT: 1" = 2'



CONTRACTOR NOTES

- 1. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PRESERVE ALL SURVEY MONUMENTS. ANY MONUMENT DISTURBED DURING CONSTRUCTION SHALL BE PERPETUATED PER THE PROFESSIONAL LAND SURVEYOR'S ACT, BUSINESS AND PROFESSIONS CODE 8771, AT THE CONTRACTORS EXPENSE.
- 2. LOCATIONS OF EXISTING UTILITIES ARE APPROXIMATED. CONTRACTOR TO FIELD VERIFY ALL EXISTING UTILITIES BEFORE COMMENCEMENT OF WORK.


GRADING NOTES

ALL SURFACE VEGETATION AND ANY MISCELLANEOUS SURFACE OBSTRUCTIONS SHOULD BE REMOVED FROM THE PROJECT AREA, PRIOR TO ANY SITE GRADING. IT IS ANTICIPATED THAT STRIPPING OF VEGETATION COULD INVOLVE THE UPPER 3 TO 5 INCHES OF THE SITE. SURFACE STRIPPINGS SHOULD NOT BE INCORPORATED INTO FILL UNLESS THEY CAN BE SUFFICIENTLY BLENDED TO RESULT IN AN ORGANIC CONTENT LESS THAN 3 PERCENT BY WEIGHT (ASTM D2974). STRIPPED TOPSOIL, WITH AN ORGANIC CONTENT BETWEEN 3 AND 12 PERCENT BY WEIGHT MAY BE STOCKPILED AND USED AS NON-STRUCTURAL FILL (I.E. LANDSCAPED AREAS). IF USED IN LANDSCAPE AREAS, SOIL WITH AN ORGANIC CONTENT BETWEEN 3 AND 12 PERCENT SHOULD BE PLACED WITHIN 2 FEET OF FINISHED GRADE AND AT LEAST 5 FEET OUTSIDE OF BUILDING PERIMETERS. SOIL WITH AN ORGANIC CONTENT GREATER THAN 12 PERCENT BY WEIGHT SHOULD BE EXCLUDED FROM FILL.

ESTIMATED EARTHWORK QUANTITIES

CUT (C.Y.): 3,398 FILL (C.Y.): 0

> NET (C.Y.): 3,398 <CUT> NOTE: QUANTITIES ARE SHOWN AS ESTIMATES ONLY. QUANTITIES SHALL NOT BE TAKEN AS EXACT QUANTITIES. CONTRACTOR SHALL BE RESPONSIBLE TO COMPLETE INDEPENDENT QUANTITY TAKE OFF AND VERIFY EARTHWORK MATERIAL TO COMPLETE THE PROJECT.








GR-1.01

CHAIN LINK FENCE

DETAILS




1 (BARBED WIRE) CHAIN LINK FENCE DETAILS


PLAN

LOCKNOG DEVICE SHALL BE APPROVED BY THE CITY EMORRER.


STORM WATER OUTFALL STRUCTURE DETAILS



TRENCH IN SURFACED & UN-SURFACED AREA DETAIL



4 TYPICAL PRECAST DROP INLET DETAIL



CONSULTING ENGINEERS

NOI

ENGINEERING PLANS FOR:
WATER TREATMENT PLANT
STORM WATER BASIN RELOCATION
SHEET TITLE:

REVISIONS

NG TAILS.DWG

ALE: AS SHOWN
B NO: 221-048
/QC: JA
E: BASIN_DETAILS.D
TE: 2/3/2023

SHEET NO.

DS-1.01

OF 7