



Addendum No. 6: Dated July 22, 2022 to bidding documents for the Town of Culpeper WWTP Improvements for the Town of Culpeper, Virginia, WW Associates Project No. 221028.00.

From: WW Associates, Inc.

To: All Bidding Document Holders of Record

This addendum forms a part of the bidding documents and modifies the drawing and specifications dated April 29, 2022. Acknowledge receipt of this addendum in the space provided on the bid form. Failure to do so may subject the bidder to disqualification.

### DRAWINGS

#### Drawing E-2 – Headworks Building #3 Power Distribution Details

Add the following note: “The 3000 AMP SWBD is existing and located in the switchboard building.”

#### Drawing E-2.1 – Drain Pump Station Building #8 Power Distribution Details

Revise Construction Note 2 as follows: “Provide (4) 4” conduits from existing junction box to “MCC8”. Provide 2 sets of 4 #500k, 1 #1/0 EGC from the existing 600A feeder in the junction box to “MCC8”. Two of the 4 conduits will remain spare. The correct breaker in the existing switchboard “SWBD” is breaker E5.

Add the following Construction Note: “3. The drawings address one 3,000 amp switchboard “SWBD”. The drain pump station is now being fed with SWBDE5 and will continue to be fed from this breaker.”

#### Drawing E-2.3 – Existing SWBD and Sludge Processing Building #12 Power Distribution Details

Add the following Construction Note: “12. Panels referenced in above notes 9, 10 and 11 will be removed when the digester building is repurposed for digester blowers.”

#### Drawing E-3 – Digesters 1 & 2 Blower Building #11 and Sludge Processing Bldg #12 Power Distribution Details

Add the following Construction Note: “15. Panels “PA7”, XFMR TR111 and panel L11 are existing and were installed in the digester building in 2007. These 2 panels and transformer shall be completely removed per the civil drawings, they will not be refed from panel “HV12”.”

End of Addendum No. 6