

**ADDENDUM NO.3
CITY OF DADE CITY
Pond Rehabilitation Project
City Project #: 2301PR
DATE: February 3, 2023**

To All Proposers: This addendum is issued to modify the previously issued documents and/or given for information purposes and is hereby made a part of the bid documents. Bidders are reminded to acknowledge receipt of this addendum, and all other addenda issued during bidding, on the bid form prior to submittal.

CLAIRFICATION:

1) N/A

RESPONSE TO QUESTIONS:

1.) What is the time frame to complete the project?

Answer: We want to start work asap but must complete by September.

2.) What is the estimated budget for the project?

Answer: \$125,000.00

3.) Is the bid one lump sum for all ponds?

Answer: Yes

4.) Is there an order that you want the ponds to be completed in?

Answer: There is no designated order

5.) Are you requesting a bid bond?

Answer: Yes

6.) Are you requesting an as build at the end of the job?

Answer: Yes

7.) Do you have a copy of the original as build?

Answer: Working on getting as built

- 8.) What are the elevations needed from Southwest Water Management for the ponds?
Answer: Elevations are based on permits and engineering drawings. There is no set elevation from SWMD.
- 9.) Is a Bid Form required?
Answer: No
- 10.) The scope was provided by a contractor previously. Did they provide pricing or just a scope?
Answer: Yes, they provided pricing and a scope.
- 11.) How many days will the contractor have to complete the project?
Answer: 180 days
- 12.) Is there any existing survey data regarding the 5 ponds?
Answer: None have been located
- 13.) Are there proposed pond bottom elevations for the 5 ponds?
Answer: Current depth minus sediment
- 14.) Will there be an oral presentation to the city?
Answer: No bid only
- 15.) Please provide the bid form reference in section 2.2 of the solicitation.
Answer: Form will not be required
- 16.) The existing addendum acknowledgement page has the year 2020, may the bidding contractor strike through this and put the current year?
Answer: Yes
- 17.) Section 2.4 Personnel and Equipment references required lawn care, flower beds and cemetery lawn care. What is the cities intent regarding this paragraph? How long shall the lawn care take place?
Answer: Please disregard this paragraph
- 18.) Due to the anticipation of addendum 1, will the city consider pushing the bid date two weeks to allow contractors time to fully understand the scope and potentially obtain the proper paperwork?
Answer: Yes, bid closing date has moved to February 14, 2023

Canal Street Pond

19.) Will we be required to flag the work area and provide road work signs?

Answer: Yes, you will follow the standard MOT guidelines.

20.) Will you require fiber or bagged on the top?

Answer: Fiber

21.) What is the size of the pipe?

Answer:

22.) Where can we put a staging area?

Answer: Northwest corner of Roosevelt Avenue & Canal Street

23.) What is the turnaround time for the road closure permits?

Answer: 1 week

24.) What is the desired width of the 70 LF gabion stone bedding and rip rap rubble at the Canal Street location?

Answer: Wide enough to prevent erosion

25.) Will the contractor be expected to desilt the canal street culvert?

Answer: No

26.) What is the proposed thickness of the 2"-4" stone & the 9"-12" riprap?

Answer: Stone 8-10" and Riprap 18-24"

Irvin Pond

27.) Who owns the utilities?

Answer: City

28.) Do we stop at the right of way?

Answer: Yes

29.) Can the water be pumped out?

Answer: Yes, from the work area to the pond

30.) What surrounding area does the City own?

Answer: Map provided

31.) What are the boundary lines?

Answer: Pond edge to CSX boundary

32.) Can the trees be taken down?

Answer: Yes, with arborist report

33.) Are there any protected species?

Answer: None known

34.) What are the details for clean up?

Answer: Restore grass. Pond should be vegetation and sediment free.

35.) What is the distance for complete renovation of this canal?

Answer: Pond edge to CSX boundary

36.) We are looking for a complete set of plans, could you please forward me the CD files for this project?

Answer: Working on getting as build

37.) What is the desired width of the 70 LF gabion stone bedding and rip rap rubble at the Irvin Pond location?

Answer: Wide enough to prevent erosion

38.) What is the proposed thickness of the 2"-4" stone & the 9"-12" riprap?

Answer: Stone 8-10" and Riprap 18-24"

Pond Avenue Pond

39.) Are we removing any trees?

Answer: No

40.) Will there be any fence work?

Answer: No

41.) Will the 2 ponds be merged together?

Answer: Yes

42.) Are we keeping the same elevation?

Answer: No, base will need sediment removed

43.) Is this a dry pond for Bahia Grass?

Answer: No

44.) At the Pond Ave. Pond, will the "Makeshift pond lift station pump & hose" removal be done by others concurrently with construction?

Answer: To remain during project

45.) What is the depth of the excess sediment that needs to be excavated and placed on the pond slopes?

Answer: Slopes need to be stable & erosion free

46.) Is the Armorflex turf mat to be install on all slopes?

Answer: Yes

47.)What is the length of the in-line yard drainpipe?

Answer: 70ft

10th Street Pond

48.) Is this a wet pond?

Answer: Yes

49.) Where are the access points?

Answer: 10th Street – Futch Street – 8th Street

50.)Are we trimming any trees?

Answer: No

51.)Where at how wide should the 980 LF of Curlex Enforcer Turf Reinforcement Matting be placed at the 10th Street Pond?

Answer: Wide enough to prevent erosion

52.)What is a 6” Sod pine?

Answer: It is a tree

53.)What is the depth of the excess sediment that needs to be excavated?

Answer: Not to exceed 1ft

Collegeview Pond

54.) Will we keep the outfall pipe?

Answer: Yes

55.) How far do you want the Rip/Rap?

Answer: Around the outfall pipe to prevent erosion

56.) Will we need to fill in any area?

Answer: No

57.) Remove Concrete?

Answer: No, Patch

58.) What is the depth of the excess sediment that needs to be excavated?

Answer: Not to exceed 1ft

59.) Is the rip rap area the same as the damaged energy dissipater that get removed?

Answer: Yes

60.)Is the riprap spec the same as the other locations?

Answer: Yes

Reminder:

The deadline for the submittals is February 14, 2023 at 2:00 pm.