

SECTION 02110

CLEARING

PART 1 GENERAL

1.01 WORK INCLUDED

- A. Clear required sites of plant life and grass.
- B. Remove root system of trees and shrubs.
- C. Remove surface debris.

1.02 RELATED WORK

- A. Section 01560 – Temporary Controls.
- B. Section 02215 - Excavation.

1.03 REGULATORY REQUIREMENTS

- A. Conform to applicable State and Local codes for disposal of debris.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.01 CLEARING

- A. Clear areas required for access to site and execution of Work.
- B. Remove trees and shrubs within designated areas. Grub out stumps, roots, and surface rock.
- C. Clear undergrowth and deadwood.
- D. Tree limbs and branches that interfere with the operation of equipment may be removed upon approval by the Engineer. A saw shall be used to make a clean cut, and limb removal shall use the three-cut method, to promote proper healing of the tree. Limbs and branches shall not be removed by pulling or tearing of the limb or branch from the tree.

3.02 PROTECTION

- A. Protect existing plant growth and features to remain upon completion of construction.
- B. Protect bench marks and existing work from damage or displacement.
- C. Maintain designated site access for vehicle and pedestrian traffic.

3.03 REMOVAL

SOUTHWEST REGIONAL WATER DISTRICT

- A. Remove debris from site.

END OF SECTION